

## **GOVERNMENT OF ANDHRA PRADESH ABSTRACT**

I & C.A.D (PW) Department – Vamsadhara Project – Restoration of damaged Jeddy Stone Apron and cement concrete Blocks on d/s of Gotta Barrage on Vamsadhara River” for an amount of Rs. 164.30 lakhs ( Rupees One Sixty Four Lakhs and Thirty Thousand Only) – Administrative Approval – Orders – Issued.

## IRRIGATION & C.A.D (P.W.VII.1) DEPARTMENT

**G.O.R.T.No. 822**

**Dated.02-12-2010.**  
**Read the following:-**

1. From the CE, North Coast,Visakhapatnam, Lr.No.CE/NC/VSP/DB/TO/ATO/BRR VDP/Vol.4/10-11, dt.17.06.2010.
  2. From the CE, (FAC),North Coast, Visakhapatnam,Lr.No.CE/NC/VSP/DB/TO/ATO/ BRRVDP/Vol.4/10-11, dt.30.09.2010.

& & &

In the reference read above, the Chief Engineer, North Coast, Visakhapatnam has reported that the Dam Safety Works Committee in the meeting held on 17.05.2010 and 21.05.2010 under the Chairmanship of Engineer-in-Chief (AW) recommended 6 Nos of works under Category-A and one work by name " Resotration of Damaged Jedy Stone Apron and Cement Concrete Blocks Apron on D/s of Gotta Barrage on Vamsadhara River" for Rs.2.41 Crores under Category 'B' of Dam Safty Works of Gotta Barrage.

The Chief Engineer , North Coast, Visakhapatnam has reported that the Jeedy Stone Apron is damaged and scoured at many locations on D/s side of the Barrage, Dumping of Jeedy Stone with new stone has been proposed under Category "A" Dam Safety Works for Rs.9.50 Lakhs and the same was recommended in the meeting. This is an emergency work to be carried out before flood season. The same will become part of the permanent work under Category-B. An estimate for the Category B works for Rs. 2.225 Crores duly deleting the Quantity proposed in Category A, is prepared. According to category "B" estimate, with the other items cement concrete Blocks Apron (Flexible Apron) and extension of dividing wall proposals made in the previous estimate are retained. The estimate is worked out for Rs. 2.225 Crores as per the Revised Standard Data and current SSR 2009-10.

The Chief Engineer, North Coast, Visakhapatnam has reported as follows:

1. The estimate for the restoration of Jeddy Stone (un coursed rubble stone of size 450 mm to 600mm) apron on D/s side of Gotta Barrage on Vamsadhara River is corrected as per specification in the approved drawing and the cross section duly adopting current SSR 2010-2011 and standard data.
  2. As per Chief Engineer, CDO drawings GTB-C-26 the length of D/s dividing wall beyond the CC Blocks will be fixed after conducting 3D modal studies and hence the same is deferred for the present.

The Chief Engineer, North Coast, Visakhapatnam has further requested that the proposal for construction of dividing wall (item B) will be taken up, after conducting 3D model studies. Hence, the estimated cost of the proposals for item A and C ie., jddy stone apron and C.C Blocks is now arrived for the following amounts.

A. Jeddy Stone apron                    Rs. 1.332 Crores  
C. C.C Blocks                            Rs. 0.312 Crores

Total: 1.643 Crores

The Chief Engineer, North Coast, Visakhapatnam has finally requested Government to accord administrative approval for Rs. 1.643 Crores and communicate the orders at the earliest.

Government after careful examination hereby accord administrative approval for the work "Restoration of damaged Jeddy Stone Apron and Cement Concrete Blocks on d/s of Gotta Barrage on Vamsadhara River" for Rs. 164.30 lakhs (Rupees One Sixty Four Lakhs and Thirty Thousand Only).

The Expenditure is chargeable for the Head of Account MH 4701-01-106 VDP – Stage-I - GH (11) -NSP - SH 26 - & D & A – 530/531 OE.

The Chief Engineer, North Coast, Visakhapatnam shall take further action accordingly.

This order issues with the concurrence of Finance (W&P) Department Vide their U.O.No.5194/F7(A1)/10-1, dated.9-11-2010.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

SHAILENDRA KUMAR JOSHI  
PRINCIPAL SECRETARY TO GOVERNMENT

To:

The Chief Engineer (FAC), North Coast, Visakhapatnam.

Copy to:

The Accountant General, A.P., Hyderabad.

The Director of Works Accounts, Hyderabad.

SF/SC.

// FORWARDED BY ORDER //

SECTION OFFICER.

